



wherever
we're
needed

Project profile

Multiple Mobile Health Units
configured to create a 12-bed ward
in a short timeframe



Project

Deployment of
multiple MHUs to
Toowoomba Hospital

Background

The infrastructure at Toowoomba Hospital is operating at capacity in a number of areas, and the hospital faces extended emergency department waiting times, emergency department overcrowding and adverse impacts on care offered. Forecast demand, driven by a growing and ageing population and high levels of chronic disease, is expected to place further pressure on the hospital.

The hospital wished to add capacity quickly through a 12-bed ward. Aspen Medical's Mobile Health Units provided a pre-fabricated solution built off site thereby reducing the disruption and noise that would normally be associated with a conventional build. From final design sign off, it took 15 weeks to construct and deploy the unit to Toowoomba Hospital. The installation time on site was minimal, being two weeks. The Aspen Medical solution is compliant to class 9A building standards.



The build includes:

- standard and disabled ensuites
- nurse station
- secure medication room
- pan room and washer
- all gasses on board
- links to Toowoomba Hospital for emergency alarms and data connections.

Challenges

- tight deadline from design through to installation
- maintain high standard against a tight timeframe.

Further enquiries

Contact our team in Business Development to discuss how we can provide you with a flexible healthcare solution.



+61 (0)2 6203 9500



businessdevelopment
@aspenmedical.com

[aspenmedical.com](https://www.aspenmedical.com)